

## NTENANCE JOIN NOW AND SAVE \$391.12

## Two (2) Seasonal System Tune-Ups

- A/C check in the spring for **EFFICIENCY**
- Furnace check in the fall for **SAFETY**

## **Trip Fee Discounts**

• \$69 (Normally \$89)

## **Service Discounts**

- 15% off repairs and replacements
- Unlocks 'Fix More, Save More' discounts for up to 18% off

Monthly \$19.99 OR Annual \$239.88



IR CONDITIONING	NON Member	JUST Membe
Log Compressor Amps	~	~
Condenser Fan Amps/Condition	~	~
Log Capacitor uF Value	~	~
Volt Drop/Inspect Contactor	~	~
Condition of Start Assist Device	~	~
Verify Proper Circuit Breaker Size to Nameplate	~	~
Verify Proper Wire Size to Unit	~	-
Inspect Condition of Outdoor Disconnect	~	-
Check Contactor	~	~
Check for Proper Refrigerant Charge with Temperature Drop	~	~
Test Compressor Windings (Mega Ohm)	~	~
Check Reversing Valve Operation (Heat Pump)	~	~
Share with Client Post Tune-Up Operation	~	~
Check for Proper Drain Flow (If Accessible)	~	~
Check for Refrigerant Leaks (If Accessible)	~	~
Install Sticker on Outdoor Unit	~	~
Outdoor Temp	×	~
Tighten Wire Connectors	×	~
Test Defrost Timer Operation	×	~
Test Reverse Valve Operation	×	~
Check Condition of Coil Fins	×	~
Low Voltage Wire Condition	×	~
Inspect Condensing Unit is Level	×	•
Inspect Shrubs are Cut Back from Unit	×	~
Check if Line is set Insulated to Condensing Unit	×	~
Clean Outdoor Condenser Coil Water Wash, Pop Top & Clean Out \$289 Value	×	~
DUCTWORK INSPECTION	NON Member	JUST Membe
Visual Inspection of Duct Work System (If Accessible)	×	~
Show Cleanliness of Ductwork	×	~
Supply Duct Installed?	×	~
Are the boots sealed to the floor?	×	~
Overall Condition of the Ductwork	×	~
Ductwork Properly Strapped Up & Sealed (If Accessible)	×	~
Return Duct Insulated?	×	~
Platform Return Needs to be Sealed?	×	-

URNACE / AIR HANDLER / EVAP COIL	NON Member	JUST Membe
Inspect All Electrical	~	-
Check Circuit Board for Burn Marks	~	-
Read Blower Motor Amps	~	-
Check Inducer Motor Amps	~	-
Blower Capacitor uF Value	~	-
Measure Temp Rise	~	-
Check Safety Switches	~	-
Check Burner Crossover Ports	~	-
Inspect Heat Exchanger	~	-
Test Gas Connection for Leaks	~	- 🗸
Any Flammable near Furnace?	~	-
Check for Proper Ignition	~	-
Test Gas Shut Off Operation	~	-
UV Germicidal Lamp Needed?	~	~
Filter Change/Clean (Customer Supplied)	~	~
Check for Proper Drain Flow	~	~
Check Temperature Rise	~	-
Test and Check All Blower Operations (No Cleaning)	~	-
Check Air Filter or Air Cleaner (No Cleaning)	~	-
Test All Drain Lines for the Evaporator	~	-
Inspect for Signs of Refrigerant Leaks	~	-
Show Owner Post Operation of Furnace	~	-
Install Sticker on Front of Furnace	~	-
Adjust Gas Pressure	×	-
Check Carbon Monoxide Detector Installed in Home	×	-
Check Evaporator Coil for Cleanliness (If Accessible) \$253 Value	×	-
Check and Tighten All Electrical Connections	×	-
Inspect Ductwork for Proper Connections and Cleanliness	×	-
Check Blower Wheel Assembly	×	-
TXV Bulb Mounted @ 10 or 2	×	-
Primary Drain Ran Correctly? (If Visible)	×	-
Secondary Drain Ran Correctly? (If Visible)	×	-
Check Condensate Pump	×	-
Inspect Drain Safety Switch	×	~
All Screws Replaced in Cabinet?	×	-
Vacuum Furnace Area and Burners	×	-
Clean Combustion Air Vent Screen	×	-
Check Hoses for Cracks and Wear	×	-
Check Pressure Switch	×	-
Check for Proper Flu Rise	×	
Inspect PVC for Leaks, etc.	×	_
Run Furnace in All Stages	×	-
Clean Outside of the Furnace	×	1
Inspect Start Collar Seal at Plenum	×	
Inspect Blower Cabinet Insulation		
•	×	
Inspect Blower Wheel Cleanliness	×	~



Sign Up at JustFixItToday.com

AIR CONDITIONING HEATING Call/Text: (281) 249-9017